



D-SITE TEST CELL
AUTOCLAVE VESSEL

- NOTE: UNLESS OTHERWISE SPECIFIED
1. ALL CABLE NUMBERS PREFIXED BY S144008.
 2. ALL HEATER/STRIPS ARE CHROMALOX 2000W P/N NS-3802-142527.
 3. * DENOTES 200°C INSULATED WIRE, TYPE SRML.
 4. GROUND WIRE SHALL BE TERMINATED ON HEATER SUPPORT STUD.
 5. FOR EQUIPMENT LOCATION AND RACEWAY , SEE DWG. SE144E020, SE144E021 & SD144E022.

COMPUTER GENERATED DRAWING - MANUAL CHANGES NOT PERMITTED	CADD FILE NUMBER SB144E008.DWG								8				4				DIV ELECTRICAL	APPROVED F. JONES		PLASMA PHYSICS LABORATORY PRINCETON UNIVERSITY NATIONAL COMPACT STELLARATOR EXPERIMENT MODULAR COILS TOOLING AND WINDING AUTOCLAVE 2000W PRIMARY HTR 13-18	NCSX SB144E008 SH 1
	7				3				ENG F.JONES	DATE 2/03											
	6				2				DR RVK CH JJN	CH JJN	SUPV JS										
	5				1				DATE 2-07-03												
	REV	DATE	BY	APPROVED	REV	DATE	BY	APPROVED													