NCSX Work Approval Form (WAF) WBS Number: 172 **WBS Title: Base Support Structures Job Numbers: 1702 and 1752 Job Title: Base Support Structure Design (1702) Job Title: Base Support Structure Procurements (1752)** Job Manager: Fred Dahlgren **Description:** This WBS element consists of the design and fabrication of the base support structure. The base support structure consists of the base column assemblies, interconnecting beams and column base hardware. Schedule: See Attached Approvals: Job Manager Date Responsible Line Manager Date **Project Manager** Date **Engineering Department Head** Date

NCSX June 2007 ETC TABLE I - DESIGN LABOR

WBS Number: 172

WBS Title: Base Support Structures

Job Numbers: 1702 and 1752

Job Title: Base Support Structure Design (1702) and Base Support Structure Procurements (1752)

Job Manager: Fred Dahlgren

Description:																				
Description.				Title I	l and II	Engine	ering f	or PF C	oils and	d Title III	Suppo	ort of Fa	bricati	ion Eff	ort.					
Task ID	41MS	<u>I</u>	48MS 37STK 37STK	35TRVL	310T	ORNL EM	ORNL DSN	EADD INOH	RSW WSWB	EMSB	EMTB	EAD*	EASB	EEEM	EESM	EETB	ECSB	ЕСТВ	RM3	Basis of Estimate
																				Based on prior engineering experiences; e.g. S-1, PLT, PDX, PBX-m
TITLE I AND TITLE II DESIGN COMPLETED Base Support layout & design Design engrg. & analysis								420				320								
PDR prep Disposition PDR chits								12				12 16								
FDR prep Prepare SOW/RFQ Disposition FDR chits								16 32				16 12 24								
Total Title I & II								480				400								
Title III Design																				
Vendor Oversight, Inspection Disposition of deviation requests and non-confort Coordination of Procurement Actions	mances											20 16 8								Engineering judgement based on recent NCSX experience Engineering judgement based on recent NCSX experience Engineering judgement based on recent NCSX experience
Subtotal Title III Design	()	0 0	0	0	0	0	0	0	0	0	44	0	0	0 0	0	0 0	0	0 0	

NCSX June 2007 ETC TABLE II- Materials and Subcontracts

WBS Title: Base Support Structures

Job Numbers: 1702 and 1752

WBS Number: 172

Job Title: Base Support Structure Design (1702) and Base Support Structure Procurements (1752)

Job Manager: Fred Dahlgren

Materials and Subcontracts (M&S)

Basis of Estimate

Description:

The base support structure is the main gravity load carrying structure (~250,000lbs) for the entire machine. It must provide the gravity load path from the machine and distribute these loads to the test cel floor. It must also be capable of withstanding horizontal seismic accelerations of 0.13g and vertical accelerations of 0.07g.

Purchased parts:	(ft.)	lbs./ft.	\$/lb.	cost	
4 - W12 x 26 x 24' - 316L stainless steel 4 - W8 x 15 x 24' - 316L stainless steel 3/4" - 316L plate 36" x 48" base hub plate 3/4" - 316L plate 36" x 48" top & bottom base column bases Weld rod & roto-bores 12 - Inconel 718 hex bolts 1-8 x 2.5" @ \$55 ea. 12 - Inconel 718 hex nuts 1-8 @ \$38 ea. 24 - 316 SS flat washers 1.03" ID @\$4.26 ea.	96 96 4 4	26 15 95 95	\$7.50 \$7.50 \$7.50 \$7.50	\$18,720.00 \$10,800.00 \$2,850.00 \$2,850.00 \$3,000.00 \$660.00 \$456.00 \$102.24	Verbal quote StainlessStructurals - recent (early April 2007) - \$/lb Verbal quote StainlessStructurals - recent (early April 2007) - \$/lb Quote , metal suppliers online - See Table V Quote , metal suppliers online - See Table V PPPL Shop estimate - see Table V - adjusted by WBS Manager Quote B&G fabricators - See Table V Quote B&G fabricators - See Table V Catalog item McMaster-Carr - see Table V
Total Materials				\$39,438.24	
Labor - PPPL:	hrs.				
Welding (4hrs @ 48 places) Welding (4hrs @ 24 places) Cut & Drill plates	192 96 75				PPPL Shop estimate - see Table V - adjusted by WBS Manager PPPL Shop estimate - see Table V - adjusted by WBS Manager PPPL Shop estimate - see Table V - adjusted by WBS Manager
Job Totals:	363				

NCSX June 2007 ETC TABLE III - Fabrication and Assembly

In-house Fabrication and Assembly and Installation

Included in Table II

NCSX June 2007 ETC

TABLE IV - Uncertainty of Estimate and Residual Risk Assessment

WBS Title: Base Support Structures

Job Numbers: 1702 and 1752

Job Title: Base Support Structure Design (1702) and Base Support Structure Procurements (1752)

Job Manager: Fred Dahlgren

Jncertainty of the Estimate	
-----------------------------	--

WBS Number: 172

	<u>High</u>	Medium	<u>Low</u>	Uncertainty Range (%)	Comments/Other Considerations
<u>Job 1702</u>				-10%/+15%	
Design Maturity		X			Design is near PDR, but nothing exotic
Design Complexity			X		Standard parts and components
Job 1752 Design Maturity Design Complexity		x	x	-10%/+15%	Design is near PDR, but nothing exotic Standard parts and components
Other Comments:					Possibility that vendor will not deliver on time, however, significant float (-4 months exist off critical path) => other vendors could be identified.

There is a finite likelihood of material costs increasing, but already assumed an escalation of ~5%/year for Inconel, HOWEVER, recent history indicatespossibility of a much higher escalation (Table V)

Note: High/Medium/Low uncertainty assessment from Job Manager. Uncertainty range based on AACEI recommended practice 18R-97 as amended for NCSX.

Residual Impac	<u>its</u>				Cost Impact	Schedule Impact	
		Likelihood of					
Job	Risk Description	Occurring	Mitigation Plan	Basis of estimate	Low High	h Low High	

Jobs 1702 and 1752 - NONE

- [1] Low cost and schedule impacts are considered the minimum (0-percentile) impacts should the event occur. High cost and schedule impacts are considered the maximum (100-percentile) impacts should the event occur
- [2] Cost impacts should be entered as man-hours (by demographic) and M&S direct cost under basis of estimate. Cost impacts should NOT include standing army costs which are separately calculated from the schedule impact Project control is reponsible for quantifying the low and high cost impacts based on the labor hours and M&S identified
- The schedule impacts should be entered as the min and max impacts on the critical path.
- If there is no critical path impact then the schedule entries should be zero.
- Likelihood of occurrence should be entered consistent with our risk classification methodology, i.e. VL= Very Likely (P>80%), L=Likely (80%>P>40%), U=Unlikley (40%>P>10%), VU=Very Unlikely (P<10%), NC=Non-credible (P<1%)

WBS Number: 172

WBS Title: Base Support Structures


Job Numbers: 1702 and 1752

Job Title: Base Support Structure Design (1702) and Base Support Structure Procurements (1752)

Job Manager: Fred Dahlgren

PPPL Engineering/Tech Shop Estimate

Metal Suppliers Internet Quote




B&G Quote

Jack McAuliffs

Fred Christin Burdensterol good

Self- Self-

Material price escalation - based on the prior 12 month history:




NICKEL PRICES

For \$1.17 Abimo. Cost escalation, based on the current price of \$23,001b, the monthly percentage rise would be 5% or ~60% per year.

Note: 1 Metric Tonne = 2200 lbs, pricing: LME (cash purchases)

Material Escalation Information




COPPER PRICES


For 10 cents/bl/mo. Cost escalation, based on the current price of \$3,64(b., the monthly percentage



ALUMINUM PRICES

Aluminum prices have been relatively stable over the past year





Activity	MILE-	Activity	Duration	Baseline Start	Baseline Finish	Shifts	Total Float	%	Proposed							
ID	stones (level 2		(work days	Start	Finish		Float	cmplt	Budgeted	FY07	FY08	FY09	FY10	FY11	FY	/12
	& 3)		,-													
17 - Crvo	stat a	and Base Support Structure														
		support Struct Design-DAHLGREN														
JOD. 1702 - 1	Dase 3	support Struct Design-DARLOKEN														
1702-510		Base support structure prel. design & analysis	40	01OCT07*	23NOV07		65		74,675.52		■EA//EM =17	78hr : EA//DM =2	24 :			
1702-510 1702-515	3	Base support structure prel. design & analysis Conduct PDR	40	01OCT07* 26NOV07	23NOV07 26NOV07		65 65		74,675.52 743.04	4		78hr ; EA//DM =2 4hr :	24 ;			
	3		40 1 40						•	- - -	EA//EM =04					
1702-515	3	Conduct PDR	1	26NOV07	26NOV07		65		743.04	- - - -	EA//EM =04	4hr ; =178hr ; EA//DM				
1702-515 1702-520	3	Conduct PDR Final design. Assy dwgs, fab dwgs, BOMs,specs/SO	1	26NOV07 27NOV07	26NOV07 01FEB08		65 65		743.04 74,675.52		EA//EM =04	4hr ; =178hr ; EA//DM				

Activity ID	MILE- stones (level 2 & 3)	Description	Duration (work days	Baseline Start	Baseline Finish	Shifts	Total Float	% cmplt	Proposed Budgeted	FY07	FY08	FY09	FY10	FY11	FY12
Job: 1752 -	Base S	upport Proc-DAHLGREN	·												
172 - Base Su	upport S	tructure													
				1	1				Γ						
161-036.8	3	Bid and award base support materials	25	15MAY08*	19JUN08		13		0.00						
161-036.9	3	Deliver base support materials	65	20JUN08	22SEP08		13		51,587.52			■ 41=39.438\$k ;			
161-037		PPPL assemble structure	35	23SEP08*	10NOV08		13		29,786.74			■EMT/TB =36	3 ;		
161-038		Title III	261	04MAR08*	19MAR09		886	LOE	8,277.26			ea//em	=44		
Subtotal			261	04MAR08	19MAR09		886		89,651.52						