

NCSX Work Approval Form (WAF)

WBS Number: 162

WBS Title: Coil Electrical Leads

Job Number: 1601-162

Job Title: Coil Electrical Leads

Job Manager: Paul Goranson

Description:

This WBS element consists of the design and fabrication of the coil electrical leads inside the cryostat which then connect the coils to the power supply bus or cables outside the cryostat.

Schedule:

See Attached

Approvals:

Job Manager

Date

Responsible Line Manager

Date

Project Manager

Date

Engineering Department Head

Date

**NCSX June 2007 ETC
TABLE I - DESIGN LABOR**

WBS Number: 162
WBS Title: Coil Electrical Leads
Job Number: 1601-162
Job Title: Coil Electrical Leads
Job Manager: Paul Goranson

Description:

This effort covers all Title I, II, and III engineering for the LN2 distribution system inside the cryostat, which includes all the necessary manufacturing and connections to interface with the cryostat LN2 supply system. This system will be fabricated in-house by PPPL. All Title III engr associated with installation is included in WBS 7.

Task ID	Multiplier	Unit	Number of		HOURS														Basis of Estimate				
			Units	Hours	ORNL EM	ORNL	DSN	ORNL	RM	EMEM	EMSM	EMSB	EMTB	EAEM	EASM	EEEM	EESM	EESB		EETB	ECEM	ECSB	ECTB
Title I and II Design																							
Pro-E models (avg)	8	hrs/model	50	400	400																		See Worksheet below - based on recent experience at MDL
assy dwgs	16	hrs/dwg	15	240	240																		See Worksheet below - based on recent experience at MDL
Detail drawings	8	hrs/dwg	40	320	320																		See Worksheet below - based on recent experience at MDL
installation dwg	16	hrs/dwg	29	464	464																		See Worksheet below - based on recent experience at MDL
cooling schematic	0	hrs/dwg	1	0	0																		See Worksheet below - based on recent experience at MDL
electrical schematic	8	hrs/dwg	14	112	112																		See Worksheet below - based on recent experience at MDL
I&C schematic	8	hrs/dwg	0	0	0																		See Worksheet below - based on recent experience at MDL
stress analysis	0	hrs/calc	0	0	0																		See Worksheet below - based on recent experience at MDL
thermal analysis	24	hrs/calc	1	24	24																		See Worksheet below - based on recent experience at MDL
special analysis (electromagnetics)	40	hrs/calc	1	40	40																		See Worksheet below - based on recent experience at MDL
Procurement Specifications	40	hrs/spec	1	40	40																		See Worksheet below - based on recent experience at MDL
preliminary and final design reviews	40	hrs/rev	1	40	40																		See Worksheet below - based on recent experience at MDL
meetings/reporting/presentations	10%	% of tot hrs		168	168																		See Worksheet below - based on recent experience at MDL
Subtotal Title I & II Design			1848	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Title III																							
vendor inspection & oversight	8	hrs per	1	8	8																		
Disposition of deviation requests and non-conformances	0.5	hrs/wk	20	10	10																		Based on recent experience on NCSX
In-House fab/assy oversight & inspection	2	hrs/wk	4	8	8																		
As-built drawings	1	hrs/dwg	84	84	84																		Based on recent experience on NCSX
Subtotal Title III Design			110	102	0	0	0	0	0	0	0	0	8	0	0	0	0	0	0	0	0	0	

Notes and worksheets

PF Coil leads

	coils at 10, 70, 130, 190, 250, 310 degrees	coils at 30, 90, 150, 210, 270, 330 degrees	coils at 50, 110, 170, 230, 290, 350 degrees	PF1+2	PF3	PF4	PF5	PF6	coils at 0, 120, 240, degrees, top and bottom	coils at 60, 180, 300 degrees Top and bottom	Outer perimeter coils	coil 1 at 10, 70, 130, 190, 250, 310 degrees	coil 2 at 30, 90, 150, 210, 270, 330 degrees	coil 3 at 50, 110, 170, 230, 290, 350 degrees	thermal transition box	total	
Pro-E models	6	6	6	1	1	1	1	1	1	1	1	1	1	1	1	50	leads modeled to create drawings, reserve space in assembly
assy dwgs	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	15	one assembly for each circuit
Detail drawings	3	3	3	2	2	2	2	2	2	2	2	2	2	2	2	40	drawings for lead length, mounting details
installation dwg	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	29	one installation dwg for each cable
cooling schematic																1	one cooling schematic for all leads
electrical schematic	1	1	1	1	1	1	1	1	1	1	1	1	1	0	14	one schematic for each circuit	
I&C schematic																	part of WBS 163
stress analysis																	
thermal analysis																1	one analysis to check temp rise, cooling
special analysis																1	one analysis for field error determination
procurement specifications																1	one specification for leads, all carry the same current, will have tl
preliminary and final design reviews																1	one review for all coil leads
meetings/reporting/presentations																10%	

**NCSX June 2007 ETC
TABLE II- Materials and Subcontracts**

WBS Number: 162
WBS Title: Coil Electrical Leads
Job Number: 1601-162
Job Title: Coil Electrical Leads
Job Manager: Paul Goranson

Description:

This effort covers all coil leads that connect the coil terminals to the buswork at the boundary of the cryostat. The lead cables are all the same except for length, and will be procured from a qualified vendor. All installation will be performed as per

Assumptions:

outside engr rate = 120 \$ per hour
 outside fab rate = 60 \$ per hour
 outside inspection/technician rate = 80 \$ per hour

TOTAL MATERIAL COST = \$86,687

Purchased parts:

set of cables	\$0
misc attachment hardware	\$11,091 @10\$/ft
thermal transition box material	\$0
<i>subtotal, purchased parts</i>	\$11,091

Lead bundles consist of six, 250 MCM cable with teflon sleeve. Lead ends are cooled by bleed liquid nitrogen supplied by the coil coolant header (WBS 161)
 Leads connect from coil terminals to buswork at bottom of machine.
 Each coil is connected separately except PF1 and PF2, which are connected in series within the central solenoid assembly

Purchased materials for in-house fabrication and sub-assembly

None required \$0
subtotal purchased materials 0

Worksheet, TF Coils:

Lead cost, TF Coils


Terminations, assembly	\$200 ea
Cable with teflon insulation, reinforced	
teflon outer jacket	\$50 per foot
Total number of cables	18
Total length of cables	277
Total cable cost	\$17,452

Geometry

radius of vertical runs	12 ft
height of upper terminals	11 ft
height of lower terminals	7 ft

Lengths

	terminal radius (m)	height from floor (ft)	cable length (ft)
coils at 10, 130, 250 degrees	3.00	11.00	12.9
coils at 70, 190, 310 degrees	3.00	7.00	8.9
coils at 30, 150, 270 degrees	3.00	11.00	16.8
coils at 90, 210, 330 degrees	3.00	7.00	12.8
coils at 50, 170, 290 degrees	3.00	11.00	22.5
coils at 110, 230, 350 degrees	3.00	7.00	18.5
Subtotals			73.9
Total length	222 ft		
25% extra for bends, offsets	55		
Total procured length	277 ft		
Avg length per cable	15 ft		



Basis of Estimate

Based on recent experiences on NCSX and UT work being done at MDL
 Based on recent experiences on NCSX and UT work being done at MDL
 Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

NCSX June 2007 ETC
TABLE II- Materials and Subcontracts

WBS Number: 162
WBS Title: Coil Electrical Leads
Job Number: 1601-162
Job Title: Coil Electrical Leads
Job Manager: Paul Goranson

Worksheet, PF Coils:


Lead cost, PF Coils

Terminations, assembly	\$200 ea
Cable with teflon insulation, reinforced	
teflon outer jacket	\$50 per foot
Total number of cables	10
Total length of cables	181
Total cable cost	\$11,052

Geometry

radius of vertical runs	10 ft
height of upper runs	12 ft
height of connection to buswork	0 ft

Lengths	terminal radius	height from	top length	bottom length
	(m)	midplane (m)	(ft)	(ft)
TF Coils				
PF1, PF2, connected in series as assy	0.00	1.30	29.7	14.3
PF3	0.00	1.30	29.7	14.3
PF4	0.69	1.60	26.5	13.0
PF5	2.23	1.50	7.6	7.6
PF6	2.80	1.00	4.1	4.1
External Trim Coils				
Mod Coils				
Subtotals			97.7	53.2
Total length	151 ft			
20% extra for bends, toroidal offsets	30			
Total procured length	181 ft			
Avg length per cable	18 ft			



Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Worksheet, Error field correction coil leads:


Lead cost, Error field coils

Terminations, assembly	\$200 ea
Cable with teflon insulation, reinforced	
teflon outer jacket	\$50 per foot
Total number of cables	2
Total length of cables	104
Total cable cost	\$5,620

Geometry

radius of vertical runs	12 ft
height of upper terminals	12 ft
height of lower terminals	6 ft

Lengths	terminal radius	height from floor	cable length
	(m)	(ft)	(ft)
coils at 0 degrees, top and bottom	3.00	12.00	13.9
Subtotals			13.9
Total length	84 ft		
25% extra for bends, offsets	21		
Total procured length	104 ft		
Avg length per cable	52 ft		



Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

NCSX June 2007 ETC
TABLE II- Materials and Subcontracts

WBS Number: 162
WBS Title: Coil Electrical Leads
Job Number: 1601-162
Job Title: Coil Electrical Leads
Job Manager: Paul Goranson

Worksheet, Mod coils:


Lead cost for modular coils

Terminations, assembly	\$200 ea
Cable with teflon insulation, reinforced	
teflon outer jacket	\$50 per foot
Total number of cables	36
Total length of cables	547
Total cable cost	\$34,529

Geometry

radius of vertical runs	12 ft
height of upper terminals	10 ft
height of lower terminals	8 ft

Lengths	terminal radius (m)	height from floor (ft)	cable length (ft)
coils at 10, 130, 250 degrees	3.00	10.00	11.9
coils at 70, 190, 310 degrees	3.00	8.00	9.9
coils at 30, 150, 270 degrees	3.00	10.00	15.8
coils at 90, 210, 330 degrees	3.00	8.00	13.8
coils at 50, 170, 290 degrees	3.00	10.00	21.5
coils at 110, 230, 350 degrees	3.00	8.00	19.5
Subtotals			72.9
Total length	219 ft		
25% extra for bends, offsets	56		
Total procured length	547 ft		
Avg length per cable	15 ft		



Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Worksheet, lead thermal transition box

66 leads, 11 to a box

	size (in)	number reqd	cost ea	total
sheet material, foil backed insul. foam	1 x 48 x 96	5	25 \$	125
end seals	1" tube x 6"	22	20 \$	440
cryo epoxy		.5 lb	28 \$	14
misc mount hardware, ss base frame			\$	500
foam caulk	16 oz	4	4 \$	16
acrylic sheet window	3/8" x 12 x 24	1	62 \$	62
assembly	40 hr each=	40		
			\$	1,157 each
number required for test floor				6
		Total hrs for fab		240
		Total M&S	\$	6,943

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

Based on recent experiences on NCSX and UT work being done at MDL

NCSX June 2007 ETC
TABLE III - Fabrication and Assembly

WBS Number: 162
WBS Title: Coil Electrical Leads
Job Number: 1601-162
Job Title: Coil Electrical Leads
Job Manager: Paul Goranson

Fabrication and Assembly

No local fab or assembly is anticipated for the Coil leads. Installation is part of WBS 7.

NCSX June 2007 ETC

TABLE IV - Uncertainty of Estimate and Residual Risk Assessment

WBS Number: 162
 WBS Title: Coil Electrical Leads
 Job Number: 1601-162
 Job Title: Coil Electrical Leads
 Job Manager: Paul Goranson

Uncertainty of the Estimate

	High	Medium	Low	Uncertainty Range (%)	Comments/Other Considerations
Design Maturity	X				Design well established based on previous devices
Design Complexity			X	-5%/+10%	Standard Components
Other Comments:					

Note: High/Medium/Low uncertainty assessment from Job Manager. Uncertainty range based on AACEI recommended practice 18R-97 as amended for NCSX.

Residual Impacts

Job	Risk Description	Likelihood of Occurring	Mitigation Plan	Basis of estimate	Cost Impact		Schedule Impact	
					Low	High	Low	High

NONE

Notes:

- [1] Low cost and schedule impacts are considered the minimum (0-percentile) impacts should the event occur. High cost and schedule impacts are considered the maximum (100-percentile) impacts should the event occur
- [2] Cost impacts should be entered as man-hours (by demographic) and M&S direct cost under basis of estimate. Cost impacts should NOT include standing army costs which are separately calculated from the schedule impact. Project control is responsible for quantifying the low and high cost impacts based on the labor hours and M&S identified
- [3] The schedule impacts should be entered as the min and max impacts on the critical path. If there is no critical path impact then the schedule entries should be zero.
- [4] Likelihood of occurrence should be entered consistent with our risk classification methodology, i.e. VL= Very Likely (P>80%), L=Likely (80%>P>40%), U=Unlikely (40%>P>10%), VU=Very Unlikely (P<10%), NC=Non-credible (P<1%)

Activity ID	MILE-stones (level 2 & 3)	Activity Description	Duration (work days)	Baseline Start	Baseline Finish	Shifts	Total Float	% cmplt	Proposed Budgeted							
										FY07	FY08	FY09	FY10	FY11	FY12	
16 - Coil Services																
Job: 1601 - Coil Services Design-GORANSON																
FY07 Rebaseline Exercise																
ECP53RBX08		FY07 Rebaseline exercise	22*	01MAY07*	31MAY07		1,333	LOE	6,228.80	ORNLEM =40hr ;						
161 - LN2 Distribution																
191-001		Title I design WBS 161 LN2 manifolds&piping	65	02JAN08*	01APR08		99		84,115.20	ORNLEM =520hr ;						
191-002	3	PDR WBS 161 LN2 manifolds&piping	1	02APR08	02APR08		99		1,294.08	ORNLEM =08hr ;						
191-011		Title II design WBS 161 LN2 manifolds&piping	65	03APR08	03JUL08		99		84,115.20	ORNLEM =520hr ;						
191-012		FDR WBS 161 LN2 manifolds&piping	1	07JUL08	07JUL08		99		1,294.08	ORNLEM =08hr ;						
191-037		Prep Req,Bid,Award-manifolds,hoses,valves etc	25	08JUL08	11AUG08		99		0.00							
191-038		Fab and deliver-manifold assy,hoses,valves etc	90	12AUG08*	18DEC08		99		140,101.51	41=59\$k ; EM/TB =492hr ; EM/EM =123hr ;						
191-031		Title III engr WBS 161	118	08JUL08	23DEC08		941	LOE	27,796.89	ORNLEM =176hr ;em/em=78;em/sm=40						
162 - Electrical Leads																
132-001		Title I design WBS 162 Coil leads	155	02JUN08*	19JAN09		49		152,991.50	ORNLEM =916hr ;						
132-002		PDR WBS 162 Coil leads	1	20JAN09	20JAN09		49		1,387.28	ORNLEM =08hr ;						
132-011		Title II design WBS 162 Coil leads	155	21JAN09	27AUG09		150		158,843.56	ORNLEM =916hr ;						
132-012		FDR WBS 162 Coil leads	1	28AUG09	28AUG09		150		1,387.28	ORNLEM =08hr ;						
132-015		Title III design WBS 162 Coil leads	99	31AUG09	29JAN10		222	LOE	19,579.88	ORNLEM =110hr ;						
132-037		Prep Req,Bid,Award Lead hardware and cables	25	31AUG09	05OCT09		150		0.00							
132-038		Deliver Lead hardware and cables	65	06OCT09	18JAN10		150		114,187.68	41=79.744\$k ;						
132-047		Prep Req,Bid,Award Material for transition box	25	31AUG09	05OCT09		216		0.00							
132-048		Deliver Material for Transition Boxes	40	06OCT09	02DEC09		216		9,909.44	41=07\$k ;						
132-049		Assemble Transition boxes (6)	40	03DEC09	08FEB10		216		20,462.40	EM/TB =240hr ;						
163 - Coil Protection System																
163.001		Design Coil protection(input to WBS 4 & 5)	65	01OCT08*	12JAN09		80		38,150.20	ORNLEM =220hr ;						
Subtotal			688	01MAY07	08FEB10		667		861,844.98							