

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 124 Vacuum Vessel Supports

#### Labor

Activity Title	Manhours	FY2003 \$\$	Labor Type	Start Date Month/Yr	End Date Month/Yr	Comments
<b>Preliminary Design (Title I)</b>						
( 50% of design schedule)	0		<i>EAEM</i>	Apr-03	Nov-03	PPPL Engineer
	0		<i>EADM</i>	Apr-03	Nov-03	PPPL Designer
	158		<i>ORNL Eng</i>	Apr-03	Nov-03	Composite of ORNL Engineer / Designer
	0		<i>ORNL Phys.</i>	Apr-03	Nov-03	Composite of ORNL Physics / scientific
	0		<i>PPPL Phys.</i>	Apr-03	Nov-03	PPPL Physics/scientific
<b>Final Design (Title II)</b>						
( 50% of design schedule)	0		<i>EAEM</i>	Dec-05	Jan-06	PPPL Engineer
	0		<i>EADM</i>	Dec-05	Jan-06	PPPL Designer
	158		<i>ORNL Eng</i>	Dec-05	Jan-06	Composite of ORNL Engineer / Designer
	0		<i>ORNL Phys.</i>	Dec-05	Jan-06	Composite of ORNL Physicist
	0		<i>PPPL Phys.</i>	Dec-05	Jan-06	PPPL Physics/scientific
<b>Lab R&amp;D labor</b>						
	0		<i>EAEM</i>	Apr-03	Nov-03	PPPL Engineer
	0		<i>EADM</i>	Apr-03	Nov-03	PPPL Designer
	0		<i>ORNL Eng</i>	Apr-03	Nov-03	Composite of ORNL Engineer / Designer
	0		<i>EASM</i>	Apr-03	Nov-03	PPPL monthly support
	0		<i>EMTB</i>	Apr-03	Nov-03	PPPL Technician
<b>Lab Fab/Assembly/Installation (Title III)</b>						
	2		<i>EAEM</i>	Jan-06	Jun-06	PPPL Engineer
	0		<i>EADM</i>	Jan-06	Jun-06	PPPL Designer
	60		<i>ORNL Eng</i>	Jan-06	Jun-06	Composite of ORNL Engineer / Designer
	6		<i>EASM</i>	Jan-06	Jun-06	PPPL monthly support
	0		<i>EMTB</i>	Jan-06	Jun-06	PPPL Technician

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 124 Vacuum Vessel Supports

#### Labor

---

*Manhours per fiscal year by labor category*

Level of Effort		FY2003	FY2004	FY2005	FY2006	FY2007	FY2008	TOTAL
PPPL Engineer	<i>EAEM</i>	0	0	0	2	0	0	2
PPPL Designer	<i>EADM</i>	0	0	0	0	0	0	0
Composite of ORNL Engineer / Designer	<i>ORNL Eng</i>	131	28	0	218	0	0	377
PPPL monthly support	<i>EASM</i>	0	0	0	6	0	0	6
PPPL Technician	<i>EMTB</i>	0	0	0	0	0	0	0
Composite of ORNL Physics / scientific	<i>ORNL Phy</i>	0	0	0	0	0	0	0
PPPL Physics/scientific	<i>PPPL Phy</i>	0	0	0	0	0	0	0

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 124 Vacuum Vessel Supports

#### M&S Costs

Activity Title	FY2003 \$\$	Comment
<b>Manufacturing Development (R&amp;D)</b>		
Purchased Design Services	\$0	
Procured Hardware/Material	\$0	
Profit at 10%	\$0	
<i>total, manf/dev (R&amp;D)</i>	\$0	w/o G&A
<b>Procured Hardware/Material</b>		
set of 12 vert.rods and hardware	\$7,757	
12 extension tubes for shell	\$7,521	
	\$0	
materials for in-house fab	\$0	
subtotal, purchased parts	\$23,319	
Profit at 10%	\$776	
<i>total, procured hdwe/matl.</i>	\$24,094	w/o G&A
<b>Purchased Design Services</b>	\$0	no purchased services anticipated
<b>Procured Installation/Assembly Costs</b>	\$0	All installation and assembly costs are included in WBS 7

#### Other Costs

Activity Title	FY2003 \$\$	Comment
Travel	\$0	No travel is anticipated for this WBS

#### Summary Costs

Activity Title	Manhours	FY2003 \$\$	Comment
----------------	----------	-------------	---------

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 124 Vacuum Vessel Supports

**Labor**

PPPL Effort	8	\$906
ORNL effort	377	\$48,984
subtotal, labor	385	\$49,890

<i>Assumed rates:</i>		<i>EASM</i> 100 \$/hr
<i>EAEM</i>	153 \$/hr	<i>EMTB</i> 73 \$/hr
<i>EADM</i>	100 \$/hr	PPPL Phys 141 \$/hr
<i>ORNL Eng</i>	130 \$/hr	ORNL Phys 160 \$/hr

**M&S, Other**

Manufacturing Development (R&D)		\$0
Procured Hardware/Material		\$24,094
Purchased Design Services		\$0
Procured Installation/Assembly Costs		\$0
Travel		\$0
subtotal, M&S		\$24,094

**G&A** \$6,024

25% on all purchased materials, subcontracts, travel

**Subtotal without contingency** \$80,008

**Contingency** \$24,002

30% Overall on this WBS

**Total cost** \$104,010

## NCSX Fabrication Project Cost and Schedule

### WBS 124 Vacuum Vessel Supports

#### Engineering, Title I, II and III

**Description:**

This effort covers all Title I, II, and III engineering for the Vacuum Vessel Supports. The supports will be procured from a qualified vendor. All installation oversight will be performed as part of WBS 7.

	multiplier	unit	no.	hours	Labor category										
					fraction	EAEM		EADM		ORNL Eng		ORNL Physics		PPPL Physics	
					fraction	fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs
<b>Title I, II design</b>															
Pro-E models	4	hrs/model	8	32	1.00	0.00	0	0.00	0	1.00	32	0.00	0	0.00	0
assy dwgs	16	hrs/dwg	2	32	1.00	0.00	0	0.00	0	1.00	32	0.00	0	0.00	0
Detail drawings	12	hrs/dwg	8	96	1.00	0.00	0	0.00	0	1.00	96	0.00	0	0.00	0
installation dwg	16	hrs/dwg	5	80	1.00	0.00	0	0.00	0	1.00	80	0.00	0	0.00	0
cooling schematic	0	hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
electrical schematic	8	hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
I&C schematic	8	hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
stress analysis	24	hrs/calc	1	24	1.00	0.00	0	0.00	0	1.00	24	0.00	0	0.00	0
thermal analysis	24	hrs/calc	1	24	1.00	0.00	0	0.00	0	1.00	24	0.00	0	0.00	0
special analysis	40	hrs/calc	0	0	1.00	0.00	0	0.00	0	0.00	0	1.00	0	0.00	0
procurement specifications	16	hrs/spec	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
preliminary and final design reviews	0	hrs/rev	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
meetings/reporting/presentations	10%	% of tot	288	29	1.00	0.00	0	0.00	0	1.00	29	0.00	0	0.00	0
<i>subtotal</i>				317			0		0		317		0		0
<b>Title III</b>															
vendor oversight, inspection	8	hrs/lot	1	8	0.00	0.00	0	0.00	0	0.00	0	0.00	0		
in-house fab/assy oversight and inspection	0	hrs/wk	4	0	1.00	0.00	0	1.00	0	0.00	0	0.00	0		
Disposition of deviation requests and non-conformances	1	hrs/wk	20	20	0.00	0.00	0	0.00	0	0.00	0	0.00	0		
As-built drawings	4	hrs/dwg	15	60	1.00	0.00	0	0.00	0	0.00	0	1.00	60		
Installation oversight and inspection	2	hrs/wk	4	8	1.00	0.25	2	0.75	6	0.00	0	0.00	0		
<i>subtotal</i>				96			2		6		0		60		

## NCSX Fabrication Project Cost and Schedule

### WBS 124 Vacuum Vessel Supports

#### Engineering, Title I, II and III

---

Schedule assumptions	start	duration (weeks)	end
Title I Design, R&D	Apr-03	6	Nov-03
Title II Design	Dec-05	6	Jan-06
Procurement	Jan-06	12	Apr-06
In-house fab / sub-assy	Apr-06	4	May-06
Installation / final assembly	May-06	4	Jun-06

#### Notes and worksheets

#### vacuum vessel supports

	total	support rods and hardware	shell extension tubes	
Pro-E models	8	4	4	
assy dwgs	2	1	1	
Detail drawings	8	4	4	
installation dwg	5	1	4	one installation drawing for each location
cooling schematic	0			
electrical schematic	0			
I&C schematic	0			
stress analysis	1	1		one stress analysis
thermal analysis	1	1		one thermal analysis
special analysis	0			
procurement specifications	0			one specification for rods, one for tubes
preliminary and final design reviews	0			review for vessel supports included in WBS 121
meetings/reporting/presentations	15%			

NCSX Fabrication Project Cost and Schedule

WBS 124 Vacuum Vessel Supports

R&D

**Description:**  
No R&D is anticipated for this WBS element, but vendor will have non-recurring engineering costs to ensure low temperature capability

**Summary**  
Purchased Design Services \$0 w/o G&A  
design rate \$120 per hour  
Procured Hardware/Material \$0 w/o G&A  
fab rate \$60 per hour  
inspection/technician rate \$80 per hour

R&D design	unit	no.	hours	Labor category												
				total fraction	EAEM fract.	hrs	EADM fract.	hrs	ORNL Eng fract.	hrs	EASM fract.	hrs	Vendor fract.	hrs		
<b>Task</b>																
Pro-E models	0 hrs/model	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
assy dwgs	0 hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
Detail drawings	0 hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
installation dwg	0 hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
cooling schematic	0 hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
electrical schematic	0 hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
I&C schematic	0 hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
special analysis	0 hrs/calc	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
procurement specifications	8 hrs/spec	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
vendor shop drawings	0 hrs/dwg	0	0	1.00										1.00	0	
vendor part programming	0 hrs/model	0	0	1.00										1.00	0	
vendor misc engineering	20% % of tot	0	0	1.00										1.00	0	
preliminary and final design reviews	0 hrs/rev	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
meetings/reporting/presentations	10% % of tot	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	0.00	0
<i>subtotal</i>			0				0		0				0			0

R&D Title III	unit	no.	hours	Labor category												
				total fraction	EAEM fract.	hrs	EADM fract.	hrs	ORNL Eng fract.	hrs	EASM fract.	hrs	EMTB fract.	hrs		
vendor oversight, inspection	0 hrs/wk	4	0	1.00	0.00	0	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
in-house fab/assy, oversight, and inspection	0 hrs/wk	4	0	1.00	0.00	0	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
Testing and experiments	0 hrs/wk	1	0	1.00	0.00	0	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0
<i>subtotal</i>			0				0		0		0		0			0

Schedule assumptions	start	duration (weeks)	end
R&D planning	Sep-03	4	Oct-03
Bid and award	Oct-03	2	Oct-03
R&D procurement / in-house fab.	Oct-03	4	Nov-03
R&D testing	Nov-03	1	Nov-03

Notes and worksheets

**WBS 124 Vacuum Vessel Supports**

**Materials and Subcontracts (M&S)**

**Description:**

This effort covers the vacuum vessel supports that connect the vessel to the modular coil shell structure. The supports will be procured from a qualified vendor. All installation will be performed as part of WBS 7.

**Assumptions:**

outside engr rate = 120 \$ per hour  
 outside fab rate = 60 \$ per hour  
 outside inspection/technician rate = 80 \$ per hour

**Purchased parts:**

set of 12 vert.rods and hardware \$7,757  
 12 extension tubes for shell \$7,521  
 Lateral supports \$5,280  
 Shell lateral brackets \$2,760

*subtotal, purchased parts* \$23,319

Leads consist of "kickless" cable with factory split terminations and gas bleed cooling  
 Leads connect from coil terminals to buswork at bottom of machine.  
 Leads will be routed to 3 locations corresponding to 3 buswork feeds for each field period

**Purchased materials for in-house fabrication and sub-assembly**

None required \$0

*subtotal purchased materials* 0

**Worksheet:**

**Vertical Rods**

no.of rods	16 ea	dia (in)	length (in)
rod weight	8 lbs	1	36
rod material cost @ 10\$/lb	\$85 per rod		
rod machining	200 per rod		
spherical bushings, nuts, etc.	\$200 per rod		
Total rod and hardware cost	\$7,757		

**Shell extension tubes**

Tube geometry	inboard 1	inboard 2	inboard 3	inboard 4
No. of tubes	6	6	6	6
dia of tubes (in)	4	4	4	4
thickness (in)	0.5	0.5	0.5	0.5
Lengths (in)	10.00	5.00	24.0	16.0
weight (lbs)	16	8	40	26
matl @ \$5/lb	\$82	\$41	\$198	\$132
machining, each	\$200	\$200	\$200	\$200
Subtotals, ea	\$282	\$241	\$398	\$332
totals by type	\$1,695	\$1,447	\$2,388	\$1,992

Total cost \$7,521

**Lateral supports**

no.of gibs	12 ea	width	length (in)	thickness
gib weight	9 lbs	3	5	2
gib material cost @ 10\$/lb	\$90 per gib			
gib machining	\$250 per gib			
special bolts	\$100 per gib			



