

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 186 Tooling Design and Fabrication

#### Labor

Activity Title	Manhours	FY2003 \$\$	Labor Type	Start Date Month/Yr	End Date Month/Yr	Comments
<b>Preliminary Design (Title I)</b>						
( 50% of design schedule)	120		<i>EAEM</i>	Apr-03	Nov-03	PPPL Engineer
	0		<i>EADM</i>	Apr-03	Nov-03	PPPL Designer
	1370		<i>ORNL Eng</i>	Apr-03	Nov-03	Composite of ORNL Engineer / Designer
	60		<i>ORNL Phys.</i>	Apr-03	Nov-03	Composite of ORNL Physics / scientific
	0		<i>PPPL Phys.</i>	Apr-03	Nov-03	PPPL Physics/scientific
<b>Final Design (Title II)</b>						
( 50% of design schedule)	120		<i>EAEM</i>	Nov-03	Jun-04	PPPL Engineer
	0		<i>EADM</i>	Nov-03	Jun-04	PPPL Designer
	1363		<i>ORNL Eng</i>	Nov-03	Jun-04	Composite of ORNL Engineer / Designer
	60		<i>ORNL Phys.</i>	Nov-03	Jun-04	Composite of ORNL Physicist
	0		<i>PPPL Phys.</i>	Nov-03	Jun-04	PPPL Physics/scientific
<b>Lab R&amp;D labor</b>						
	160		<i>EAEM</i>	Apr-03	Nov-03	PPPL Engineer
	0		<i>EADM</i>	Apr-03	Nov-03	PPPL Designer
	259		<i>ORNL Eng</i>	Apr-03	Nov-03	Composite of ORNL Engineer / Designer
	72		<i>EASM</i>	Apr-03	Nov-03	PPPL monthly support
	168		<i>EMTB</i>	Apr-03	Nov-03	PPPL Technician
<b>Lab Fab/Assembly/Installation (Title III)</b>						
	126		<i>EAEM</i>	Jul-04	Oct-06	PPPL Engineer
	0		<i>EADM</i>	Jul-04	Oct-06	PPPL Designer
	446		<i>ORNL Eng</i>	Jul-04	Oct-06	Composite of ORNL Engineer / Designer
	494		<i>EASM</i>	Jul-04	Oct-06	PPPL monthly support
	1344		<i>EMTB</i>	Jul-04	Oct-06	PPPL Technician

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 186 Tooling Design and Fabrication

#### Labor

*Manhours per fiscal year by labor category*

Level of Effort		FY2003	FY2004	FY2005	FY2006	FY2007	FY2008	TOTAL
PPPL Engineer	<i>EAEM</i>	240	174	56	56	0	0	526
PPPL Designer	<i>EADM</i>	0	0	0	0	0	0	0
Composite of ORNL Engineer / Designer	<i>ORNL Eng</i>	1393	1649	198	198	0	0	3438
PPPL monthly support	<i>EASM</i>	62	66	219	219	0	0	566
PPPL Technician	<i>EMTB</i>	144	175	597	597	0	0	1512
Composite of ORNL Physics / scientific	<i>ORNL Phy</i>	51	69	0	0	0	0	120
PPPL Physics/scientific	<i>PPPL Phy</i>	0	0	0	0	0	0	0

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 186 Tooling Design and Fabrication

#### M&S Costs

Activity Title	FY2003 \$\$	Comment
<b>Manufacturing Development (R&amp;D)</b>		
Purchased Design Services	\$0	
Procured Hardware/Material	\$124,000	
Profit	\$0	profit already included in these items
<i>total, manf/dev (R&amp;D)</i>	\$124,000	w/o G&A
<b>Procured Hardware/Material</b>		
Tooling assy fixtures, misc. equipment	\$261,500	
General procurements	\$20,000	
Welding tools, materials and equipment	\$25,000	
Welding tools, materials and equipment	\$20,000	
Profit at 10%	<u>\$32,650</u>	
<i>total, procured hdwe/matl.</i>	\$359,150	w/o G&A
<b>Purchased Design Services</b>	\$0	no purchased services anticipated
<b>Procured Installation/Assembly Costs</b>	\$0	All installation and assembly costs are included in WBS 7

#### Other Costs

Activity Title	FY2003 \$\$	Comment
Travel	\$10,000	one trip per major fixture

## NCSX Fabrication Project Cost and Schedule Estimating Form

### WBS 186 Tooling Design and Fabrication Summary Costs

Activity Title	Manhours	FY2003 \$\$	Comment
<b>Labor</b>			
PPPL Effort	2,604	\$247,469	<i>Assumed rates:</i> <i>EAEM</i> 153 \$/hr <i>EADM</i> 100 \$/hr <i>ORNL Eng</i> 130 \$/hr <i>EASM</i> 100 \$/hr <i>EMTB</i> 73 \$/hr PPPL Phys 141 \$/hr ORNL Phys 160 \$/hr
ORNL effort	3,558	\$466,192	
subtotal, labor	6,162	\$713,661	
<b>M&amp;S, Other</b>			
Manufacturing Development (R&D)		\$124,000	
Procured Hardware/Material		\$359,150	
Purchased Design Services		\$0	
Procured Installation/Assembly Costs		\$0	
Travel		\$10,000	
subtotal, M&S		\$493,150	
<b>G&amp;A</b>		\$123,288	25% on all purchased materials, subcontracts, travel
<b>Subtotal without contingency</b>		\$1,330,099	
<b>Contingency</b>		\$532,039	40% Overall on this WBS
<b>Total cost</b>		\$1,862,138	

NCSX Fabrication Project Cost and Schedule

WBS 186 Tooling Design and Fabrication

In-house Fabrication and Assembly

Description:

This effort covers all PPPL effort involved with preparing the facility space for field period assembly. There is very little area prep to do after the test cell is made ready for coil winding.

Labor category

Sub-assembly	multiplier	unit	no.	hours	total fraction	EAEM		EASM, EMSM		EMTB		EADM	
						fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs
Installation of VV fixtures	80	ea	3	240	1.00	0.00	0	0.20	48	0.80	192	0.00	0
installation of mod coil fixtures	80	ea	2	160	1.00	0.00	0	0.20	32	0.80	128	0.00	0
installation of TF coil fixtures	80	ea	1	80	1.00	0.00	0	0.20	16	0.80	64	0.00	0
misc fab/assembly on site	1200		1	1200	1.00	0.00	0	0.20	240	0.80	960	0.00	0
				0	1.00	0.00	0	1.00	0	0.00	0	0.00	0
				0	1.00	0.00	0	0.00	0	1.00	0	0.00	0
<b>subtotal</b>				<b>1680</b>			<b>0</b>		<b>336</b>		<b>1344</b>		<b>0</b>

  

	total fraction	EAEM		EASM, EMSM		EMTB		EADM	
		fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs
0	1.00	0.00	0	1.00	0	0.00	0	0.00	0
0	1.00	0.00	0	0.00	0	1.00	0	0.00	0
0	1.00	0.00	0	1.00	0	0.00	0	0.00	0
0	1.00	0.00	0	0.00	0	1.00	0	0.00	0
0	1.00	0.00	0	1.00	0	0.00	0	0.00	0
<b>subtotal</b>	<b>0</b>		<b>0</b>		<b>0</b>		<b>0</b>		<b>0</b>

Schedule assumptions

	start	duration (weeks)	end
Title I Design, R&D	Aug-03	10	Sep-03
Title II Design	Oct-03	26	Apr-04
Procurement	Apr-04	22	Oct-04
In-house fab / sub-assy	Oct-04	48	Sep-05
Installation / final assembly	Feb-05	67	Jun-06

Notes and worksheets

Field Period Assembly Area Preparation

Ref J. Chrzanowski spreadsheet, April 2003

This proposal includes the costs associated with the fabrication of (18) Modular coils for the NCSX Machine. This includes inspection of the conductor and castings, coil winding, VPI and Testing activities.

activity	Duration	Start	End	HP	Safety	IH	QC	EAEM	EADM	EMSM	EMTB	M&S	M&S
ID	Days			hours	hours	hours	hours	hours	hours	hours	hours	w/o G&A	w/G&A
<p><b>Notes:</b> A number of activities can be performed in parallel and are not series activities during the field period assemblies.</p> <p>a) The TF coil sub-assembly</p> <p>b) The sub-assembly of the modular coils</p> <p>c) Preparation of the vacuum vessel for assembly</p>													
<p><b>## Tooling Design and Fabrication</b></p> <p>1) Task involves the design, fabrication and procurement of tooling and equipment to assemble the field period assemblies</p> <p>2) Fixtures include:</p> <p>a) (2) Mod. Coil sub assy. Stands</p> <p>b) (2) TF coil stands</p> <p>c) (3) VV stands</p> <p>d) (1) Mod. Coil assy fixture</p>													
Final tooling design	165	3-Oct-03	1-Jun-04	Cost in Engr				432	1000				
Lab fabrication/assy./installation	273	2-Jun-04	30-Jun-05					30		400	1728		
Tooling assy fixtures, misc. equipment	273	2-Jun-04	30-Jun-05	Cost in M&S									
General procurements	439	1-Oct-04	30-Jun-06	Cost in M&S									
Welding tools, materials and equipment	252	2-Jun-04	30-Sep-06	Cost in M&S									
				0	0	0	0	462	1000	0	400	1728	0

## NCSX Fabrication Project Cost and Schedule

### WBS 186 Tooling Design and Fabrication

#### Materials and Subcontracts (M&S)

---

**Description:**

This effort covers all M&S required for Field Period Assembly Planning and Oversight

**Assumptions:**

outside engr rate = 120 \$ per hour  
 outside fab rate = 60 \$ per hour  
 outside inspection/technician rate = 80 \$ per hour

**Purchased parts:**

*subtotal, purchased parts*                      **\$0**

**Purchased materials for in-house fabrication and sub-assembly**

Tooling assy fixtures, misc. equipment            \$261,500  
 General procurements                              \$20,000  
 Welding tools, materials and equipment        \$25,000

*subtotal purchased materials*            **\$306,500**

**Worksheet:**

**Tooling assy fixtures, misc. equipment**

	unit cost	unit	no.	total	remarks
VV supporting fixture	\$25,000	ea	3	\$75,000	supports vv segment
modular coil 3-coil sub-assy frame	\$8,000	ea	2	\$16,000	assembles three coils into sub assembly
modular coil 3-coil sub-assy manipulator	\$100,000	ea	1	\$100,000	6 axis controlled motion
modular coil temporary support fixtures	\$15,000	ea	3	\$45,000	jacks and frames for supporting mod coils
TF coil sub-assembly frame	\$8,000	ea	1	\$8,000	TBD
TF coil 3-coil assembly manipulator	\$0	ea	0	\$0	use crane
full field period support fixture	\$2,500	lot	3	\$7,500	blocks from floor to TF structure
VV port welding fixtures	\$10,000	lot	1	\$10,000	clamps and supports to position port extensions
<b>subtotal</b>				<b>\$261,500</b>	

**General procurements**

slings, swivels, chain-falls, etc.	\$10,000	lot	1	\$10,000	
Leak check bags, tape, hoses, etc.	\$5,000	lot	1	\$5,000	
Mass Spec leak detector	\$0	ea	1	\$0	on hand
vacuum pumps	\$0	ea	1	\$0	on hand
bakeout lines	\$5,000	lot	1	\$5,000	
<b>subtotal</b>				<b>\$20,000</b>	

**Welding tools, materials and equipment**

Narrow gap TIG welding tools	\$7,500	ea	2	\$15,000	
welding consumables	\$10,000	lot	1	\$10,000	
<b>subtotal</b>				<b>\$25,000</b>	



## NCSX Fabrication Project Cost and Schedule

### WBS 186 Tooling Design and Fabrication

#### Engineering, Title I, II and III

---

**Description:**

This effort covers all Title I, II, and III engineering for the field period subassembly tooling and fixtures

**Labor category**

	multiplier	unit	no.	hours	Labor category											
					total fraction	EAEM		EADM		ORNL Eng		ORNL Physics		PPPL Physics		
					fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs		
<b>Title I, II design</b>																
Pro-E models (avg)	16	hrs/model	40	640	1.00	0.00	0	0.00	0	1.00	640	0.00	0	0.00	0	
assy dwgs	20	hrs/dwg	20	400	1.00	0.00	0	0.00	0	1.00	400	0.00	0	0.00	0	
Detail drawings	20	hrs/dwg	42	840	1.00	0.00	0	0.00	0	1.00	840	0.00	0	0.00	0	
installation dwg	20	hrs/dwg	9	180	1.00	0.00	0	0.00	0	1.00	180	0.00	0	0.00	0	
cooling schematic	20	hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	
electrical schematic	20	hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	
I&C schematic	20	hrs/dwg	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	
stress analysis	24	hrs/calc	8	192	1.00	0.00	0	0.00	0	1.00	192	0.00	0	0.00	0	
thermal analysis	40	hrs/calc	0	0	1.00	0.00	0	0.00	0	1.00	0	0.00	0	0.00	0	
special analysis (electromagnetics)	40	hrs/calc	3	120	1.00	0.00	0	0.00	0	0.00	0	1.00	120	0.00	0	
procurement/fab specifications	40	hrs/spec	8	320	1.00	0.75	240	0.00	0	0.25	80	0.00	0	0.00	0	
preliminary and final design reviews	40	hrs/rev	3	120	1.00	0.00	0	0.00	0	1.00	120	0.00	0	0.00	0	
meetings/reporting/presentations	10%	% of tot	2812	281	1.00	0.00	0	0.00	0	1.00	281	0.00	0	0.00	0	
<i>subtotal</i>				3093			240		0		2733		120		0	

	multiplier	unit	no.	hours	Labor category										
					total fraction	EAEM		EASM		EADM		ORNL Eng			
					fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs	fract.	hrs	
<b>Title III</b>															
vendor oversight, inspection	4	hrs/wk	22	89	1.00	0.50	44	0.00	0	0.00	0	0.50	44		
Disposition of deviation requests and non-conformances	1	hrs/wk	147	147	1.00	0.20	29	0.00	0	0.00	0	0.80	118		
As-built drawings	4	hrs/dwg	71	284	1.00	0.00	0	0.00	0	0.00	0	1.00	284		
Installation oversight and inspection	4	hrs/wk	53	210	1.00	0.25	53	0.75	158	0.00	0	0.00	0		
<i>subtotal</i>				730			126		158		0		446		

Schedule assumptions	start	duration (weeks)	end

## NCSX Fabrication Project Cost and Schedule

### WBS 186 Tooling Design and Fabrication

#### Engineering, Title I, II and III

Title I Design	Apr-03	31	Nov-03
Title II Design	Nov-03	30	Jun-04
Procurement	Jul-04	22	Dec-04
In-house fab / sub-assy	Jan-05	72	May-06
Installation / final assembly	Sep-05	53	Oct-06

#### Notes and worksheets

	total	VV holding fixture	3-mod-coil assy fixture	3-mod-coil manipulating fixture	modular coil temporary support fixtures	TF coil sub-assembly frame	TF coil 3-coil assembly manipulator	full field period support fixture	VV port welding fixtures
Pro-E models	40	4	4	6	4	4	4	4	10
assy dwgs	20	2	2	4	2	2	2	2	4
Detail drawings	42	4	4	8	4	4	4	4	10
installation dwg	9	1	1		1	1		1	4
cooling schematic	0								
electrical schematic	0								
I&C schematic	0								
stress analysis	8	1	1	1	1	1	1	1	1
thermal analysis	0								
special analysis	3	1			1			1	seismic analysis
procurement specifications	8	1	1	1	1	1	1	1	1
preliminary and final design reviews	3	1		1			1		
meetings/reporting/presentations	15%								