

## B1 and B2 Counterbore Rework



In order to expedite the rework of B1 and B2, MTM is requesting the option to bore the counterbore relief completely through the area in red (from the top of the support leg to the counterbore). The cut would extend into the leg approximately 1.3" over a distance of 8.5" to the counterbore face. This applies to hole 11 in the D flange only.

