

# Job 1260 Neutral Beam Transition Duct (NBTD)

P. L. Goranson






# **Functional requirements**



- NBTD provides interface for:
- Man access into Vacuum Vessel (opening 13.5" wide x 34" tall)
- Mounting vacuum pumping system (13.5" id Port)
- Mounting Neutral Beam units
- Mounting diagnostics
- Mounting Lateral Supports and positioning
   VV toroidally
- In addition, the NBTD must penetrate and seal to the Cryostat.
- NBTD operates at 350C at its mounting flange during bakeout; most of construction must be Inconel.







# **Design Status**




- Models were completed (2003) and were reviewed several years ago
  - Must reaffirm design, hold peer review and work toward SRD
  - A PDR is required
- Baseline was changed for a time to incorporate simplified ducts (Man Access Ports) which did not mount NB's.
- Lateral support drawings were completed.





# **NBTD** showing Lateral Supports













# **NBTD Preliminary Drawings**





**TOP VIEW** 









## **Labor Cost**



Title I an II Design												
Peer Review to Establish Requirements												
Review and Update Assbly Dwgs												
Prepare for PDR Neutral Beam Transition Duct												
PDR for NBTD	0											
Resolve PDR Chits	40											
Review and Update Port Mod Dwg	40											
Review and Update Large Rect Port Dwg												
Review and Small Large Rect Port Dwg	40											
Review and Update Weldment Dwgs Review and Update Misc Det & Cuts Dwgs Review of Drawings												
							Stress analysis					
							Prepare for FDR Neutral Beam Transition Duct	40				
Final Design Review	0											
Resolve PDR Chits												
Subtotal Title I & II Design												
	800											
Title III												
Disposition of deviation requests and non-conformances												
Update of drawings as Needed												
Procurement coordination												
Subtotal Title III Design	140											

#### **Based in recent MDL & NCSX experience**

Assume 2 drawings @ 40 hr each - based on MDL & NCSX experience

Based in recent MDL & NCSX experience

Milestone - no resources

#### Based in recent MDL & NCSX experience

Assume 1 drawing @ 40 hr each - based on MDL & NCSX experience Assume 1 drawing @ 40 hr each - based on MDL & NCSX experience Assume 1 drawing @ 40 hr each - based on MDL & NCSX experience Assume 3 drawings @ 40 hr each - based on MDL & NCSX experience Assume 2 drawings @ 20 hr each - based on MDL & NCSX experience Assume 2 people for ~1/2 Weeks - based on MDL & NCSX experience

Based in recent MDL & NCSX experience Based in recent MDL & NCSX experience Based in recent MDL & NCSX experience Based in recent MDL & NCSX experience

Based in recent MDL & NCSX experience Based in recent MDL & NCSX experience Based in recent MDL & NCSX experience






# **M&S Cost**



Costs reflects recent significant increase in Inconel price. Lateral supports added.

This element consists of the port duct, seals, and all cover flanges weight of shell assembly, with ports \$/lb for fabrication		es recent vendor Inconel quotes
subtotal, fab cost shell	\$71,400	
Ports 8" o.d. flange, 6" tube 8" o.d. rotatable cover flange no. of 8" ports cost for 8" ports	225\$/ea 125\$/ea 7ea \$2,450	MDC catalog 10 MDC catalog 10
14.5" x 16.5" flange with tube(ss)	1500 \$/ea	NCSX/MDL experience
blank 14.5" x 16.5" flanges(ss)	1000 \$/ea	NCSX/MDL experience
no. of 14.5" x 16.5" ports	2ea	•
cost for 14.5" x 16.5" ports 16.5" o.d. flange, 14" tube 16.5" o.d. rotatable cover flange no. of 16.5" ports cost for 16.5" ports	\$5,000 1000 \$/ea 710 \$/ea 2ea \$3,420	MDC catalog 10
large square flange cover, ss o-ring seals for diamond flange and square flange	\$4,000 \$2,530	
subtotal, ports	\$17,400	
Fabricate and install lateral support	\$8,000\$/ea	
number of supports	2 ea	
subtotal for support	\$16,000	
Total, each nbi port duct extension no. of nbi duct extensions	<b>\$104,800</b> 3	
total, 3 extensions	\$314,400	





# Schedule & Staffing



#### **Schedule**

Activity ID	MILE -STONE	Activity Description	Duration (work	SHIFTS	Forecast Start	Forecast Finish	Total Float	Cost to Complete	FY08 FY09 FY10
1260-90	LEVEL	Prep for PDR	days 65		30JUN08	30SEP08	318	30,200.00	omlem=200
1260-95		PDR	0			30SEP08	318	0.00	
1260-100		Design Update and review	65		01OCT08*	12JAN09	318	99,486.80	ornlem=440;ea//em=160
1260-110		FDR	0			12JAN09	318	0.00	
1260-120		Requisition, Bid and Award Duct contract	40		13JAN09	09MAR09	318	0.00	
1260-130		Fabr &deliver 3 port duct extensions incl suprts	260		01OCT09*	18OCT10	174	420,831.66	41=\$314.4k
1260-140		Title III	402		13JAN09	18AUG10	1,054	16,188.70	ORNLEM =100hr :

## **Staffing**

P. L. Goranson – 80% during Title I & II design.

**Gary Lovett – 100% during Title I & II.** 





#### **Schedule and Cost Risk**



#### **Uncertainty of the Estimate**

High Medium Low Range (%)

Design Maturity X

Design Complexity X

Uncertainty Range (%)

-10%/+15%

Other Comments:

### **Mitigation**

**Cost Impact** Schedule Impact Likelihood **Mitigation Plan** Job **Risk Description** of Occurring Basis of estimate Low High Low High 1260 Design is vintage and revisit could result in criteria U Schedule was made more Engineering hours to redo 200 hrs 400 hrs 0 changes, i.e. diagnostic requirements, number of models and hold design aggressive with early start to ORNL EM ORNL EM ports, NB alignment, further design review, etc. assure ageement with design. review.



